

PROPERTY DEVELOPMENT, MALLOW

ALU-CAST ENTERPRISES



Forefront Construction has been leading a recent project in the North Cork town of Mallow and Alu-Cast Enterprises have been delighted to be part of such a unique and development. The Cork-based construction company has set out to build a total of 13 homes on their plot, varying from dormer bungalows to large two-story houses for its customers.

Alu-Cast's sales team spent some time with the developers to try and establish what would be the best product for the build and it was agreed with the engineers and the architects that the Extruded Cast Gutter would be the best option. The 5" HR coated cast gutter, which came pre-made in 3-metre lengths, was fitted by using standard extruded brackets along with a high-grade silicone sealant to help prevent against leaks. To complete the development Alu-Cast will fit 3" round downpipes, which are swaged to allow for a cleaner look as each pipe seamlessly passes into the next. Each pipe is secured to the wall with 8x60mm wall plugs and two stand-off brackets per pipe.



<https://alucast.ie/>